BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of the work: **Estimate for Providing Cement Concrete Road behind Govt. School in Kodigehalli Village in Ward No. 08, Kodigehalli Sub Division.**

							Estimate Cost:		3000000.00
Sl. No	Description	Unit	No.	L	B	D	Qty	Rate	Amount
1	KSRB 2-1.1: Earth work in surface excavation in **ordinary soil** for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1, **No. 5/ Item No. 2.1/ PWD SR 2013-14**	Cum							
	behind Govt. School, Kodigehalli Village		1	95.00	3.50	0.30	99.75		
			1	60.00	4.00	0.35	84.00		
			1	80.00	4.00	0.35	112.00		
			1	75.00	4.00	0.35	105.00		
			1	35.00	3.80	0.35	46.55		
							447.30	126.36	**56521.00**
	Basic Rate	117.00							
	Area Weightage @8%	9.36							
	Total	**126.36**							
2	KSRB 2-2.2 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, **in Hard soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, **Page No. 5 / Item No. 2.4 / PWD SR 2013-14**	Cum							
	RCC Drain		1	32.00	1.00	0.90	28.80		
	Culvert		2	6.00	2.00	0.90	21.60		
							50.40	227.88	**11485.00**
	Basic Rate	211.00							
	Area Weightage @ 8%	16.88							
	Total	**227.88**							
4	KSRB 4-1.3 : Providing and laying in position **plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs** using **40mm** and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, **in foundation and plinth**, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 **Page No. 12 /Item No. 4.3 PWD SR - 2013-14**	Cum							

Sl. No	Description	Unit	No.	L	B	D	Qty	Rate	Amount
	behind Govt. School, Kodigehalli Village		1	95.00	3.50	0.15	49.88		
			1	60.00	4.00	0.15	36.00		
			1	80.00	4.00	0.15	48.00		
			1	75.00	4.00	0.15	45.00		
			1	35.00	3.80	0.15	19.95		
	RCC Drain		1	32.00	1.00	0.15	4.80		
	Culvert		2	6.00	2.00	0.15	3.60		
							207.23	4290.84	**889169.00**
	Basic Rate	3973.00							
	Area Weightage @ 8%	317.84							
	Total	**4290.84**							
5	KSRB 5.4-3: Providing and constructing granite / trap / basalt size stone masonry in **superstructure with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 **Page No. 26 / Item No. 5.12/ PWD SR 2013-14**	Cum							
	Culvert		2x2	6.00	0.60	0.80	11.52		
							11.52	4423.68	**50961.00**
	Basic Rate	4096.00							
	Area Weightage @ 8%	327.68							
	Total	**4423.68**							
6	KSRB 15.1.3: Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. **Page No. 122 / Item No. 15.3 / PWD SR 2013-14**	Sqm							
	Culvert		2x2	6.00		0.80	19.20		
							19.20	77.76	**1493.00**
	Basic Rate	72.00							
	Area Weightage @ 8%	5.76							
	Total	**77.76**							
7	KSRB 4-1.6 : Providing and laying in position plain cement concrete of **mix M15 with cement @ 240 kgs with 20mm** and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2. **No. 12 / Item No. 4.6 / PWD SR 2013-14**	Cum							
	Culvert Coping		2x2	6.00	0.60	0.10	1.44		
			2x2	6.00	0.35	0.15	1.26		
							2.70	4779.00	**12903.00**
	Basic Rate	4425.00							
	Area Weightage @ 8%	354.00							
	Total	**4779.00**							

Sl. No	Description	Unit	No.	L	B	D	Qty	Rate	Amount
8	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for **vertical surface** such as **walls at any thickness**, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 **Page No.17 / Item No. 4.31 PWD SR - 2013-14**	Sqm							
	For RCC Drain Side Walls		4	32.00		0.60	76.80		
	Culvert Covering Slabs		20	4.80		0.23	22.08		
							98.88	271.08	**26804.00**
	Basic Rate	251.00							
	Area Weightage @ 8%	20.08							
	Total	**271.08**							
9	KSRB 4.2.2 : Providing and laying in position **reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm** and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum wuth superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works **in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall** (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.6 **Page No. 13 / Item No. 4.11 PWD SR - 2013-14**	Cum							
	RCC Drain Bottom		1	32.00	0.90	0.15	4.32		
	Side Walls		2	32.00	0.15	0.60	5.76		
	Covering Slab		1	32.00	0.60	0.10	1.92		
	Culvert Covering Slab		2	6.00	1.80	0.23	4.97		
							16.97	5639.76	**95695.00**
	Basic Rate	5222.00							
	Area Weightage @ 8%	417.76							
	Total	**5639.76**							
10	KSRB 4.9.2 : Providing **T.M.T steel reinforcement for R.C.C** work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 **Page No. 19 / Item No. 4.46.2 PWD SR 2013-14 TMT bar Fe 500**	Qntl							
	Consider 70 Kg/Cum		0.60	16.97			10.18		
			13.85	4.00			55.40		

Sl. No	Description	Unit	No.	L	B	D	Qty	Rate	Amount
							65.58	7450.92	**488637.00**
	Basic Rate	6899.00							
	Area Weightage 8%	551.92							
	Total	**7450.92**							
11	KSRRB M2600-3: Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical specification complete as per specifications, MORTH specification No. 2605, **No. 251 / Item No. 31.3 PWD SR 2013-14**	M							
			50	3.80			190.00		
							190.00	137.16	**26060.00**
	Basic Rate	127.00							
	Area Weightage @ 8%	10.16							
	Total	**137.16**							
12	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. **Page No. 19 / Item No. 4.48.1/ PWD SR 2013-14**	Cum							
	behind Govt. School, Kodigehalli Village		1	95.00	3.50	0.10	33.25		
			1	60.00	4.00	0.10	24.00		
			1	80.00	4.00	0.10	32.00		
			1	75.00	4.00	0.10	30.00		
			1	35.00	3.80	0.10	13.30		
							132.55	6464.88	**856920.00**
	Basic Rate	5986.00							
	Area Weightage @ 8%	478.88							
	Total	**6464.88**							
13	**Vaccum De-watering** with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift No. **190 / Item No. 22.7/ PWD SR 2013-14**	Sqm							

Sl. No	Description	Unit	No.	L	B	D	Qty	Rate	Amount
	behind Govt. School, Kodigehalli Village		1	95.00	3.50		332.50		
			1	60.00	4.00		240.00		
			1	80.00	4.00		320.00		
			1	75.00	4.00		300.00		
			1	35.00	3.80		133.00		
							1325.50	91.80	**121681.00**
	Basic Rate	85.00							
	Area Weightage @ 8%	6.80							
	Total	**91.80**							
14	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)	Cum							
				Vide Item No. 1			**486.90**	72.71	**35400.00**
	Basic rate for haulage of materials as per item no.17.4 page 141) Rs. 2.00								
	Average weight of earth 1.28 tonne / kg for 2X1.28X15.00=5.12	5.12							
	Add loading and unloading Vide item no.17.1 P.no.141	62.20							
		67.32							
	Area Weightage @ 8%	5.39							
	Total	**72.71**							
15	**Sub Total**								**2678498.00**
16	KRIDL Service Charges and Applicable Taxes @ 11%								**294635.00**
17	For Third Party QC Charges @ 1%								**26785.00**
18	Miscellaneous and other Charges	L/S							**82.00**
								Total	**3000000.00**

(Rs. Thirty Lakhs Only)

ADMINISTRATIVELY SANCTIONED FOR Rs .... Thirty Lakhs
Under H/A P.1878 22.75 -
Registered as EE ( ) No. ....
Subject to conditions ... in enclosed memo EE ( ) No. ... /01.... Dt ... Sanctioned dated ...
Addl Commnr (ys) / AS-889 / 13-14 dt 22/2/2014 Rs 30.00 Lakhs
Joint Commissioner (Yelahanka Zone) BBMP, Bengaluru-92

CERTIFICATE:

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per P.W.D S.R of 2013-14.
3 The provisions were made in this estimate are necessary and adequate.
4 This works come under B.B.M.P. limits.

Assistant Engineer

Assistant Executive Engineer
Bruhat Bangalore Mahanagara Palike
Kodigehalli Sub Division

Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Division

Technical Sanction for Rs. 30.00 Lakhs
Thirty Lakhs only
SE/YNK/289/13-14, 03/03/14
22-75 % Grant.
Registered as SE No: ..... Dated ..... Subject to
to conditions contained enclosed memo.
No: ..... Dr.
AEE
EE (BTP Div.)